



FLOOR DIAPHRAGM

FRAMING SCHEDULE

1. ALL DOOR & WINDOW HEADERS TO BE 4x8 D.F. #2 UNLESS OTHERWISE NOTED
2. PROVIDE 2x8 R.S. FASCIAS @ ALL NEW RAFTER TAILS
3. ALL DOOR & WINDOW KING-POSTS TO BE 2x D.F. #2 W/TRIMMERS (OBL. 2x5 @ +6-0" OPENINGS
4. ALL TRUSS DESIGN & SPEC.'S SHALL BE PROVIDED BY TRUSS MFGR. PROVIDE STANDARD LATERAL BRACING.
5. TYPICAL ROOF COVER SHALL INCLUDE: CONC. SPANISH TILES 0/40# FELT 0/ROOF DIAPHRAGM SHEATHING
6. SEE U.B.C. TABLE 25-g FOR TYPICAL NAILING SCHEDULE FOR ALL FRAMING MEMBERS & SHEATHING TO WOOD SUPPORTS
7. SEE U.B.C. TABLE 47-c FOR TYP. FASTENING SCHEDULE FOR LATH & PLASTER TO WOOD SUPPORTS
8. SEE U.B.C. TABLE 47-g FOR TYP. NAILING SCHEDULE FOR GYPSUM BD. TO WOOD SUPPORTS
9. HATCHED WALLS INDICATE SHEAR WALLS (SEE SCHEDULE).

GENERAL NOTES:

THE HUDDLESTONS
CEDAR CITY
UTAH



D. SHANE
AVERY

DESIGNER - DRAFTSMAN - TRADERMAN
"At Your Service"

457-1484

4801 Meadow Way #B Las Vegas, NV 89121

CUSTOM HOME FOR THE HUDDLESTONS

DO NOT SCALE DRAWINGS
ALL WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DRAWINGS. VERIFY ALL DIMENSIONS PRIOR TO START OF CONSTRUCTION. NOTIFY THE ARCHITECT OF ANY DIMENSIONAL ERRORS.

[illegible]

JOB #	0000
FILE	MAP-00
DATE	8-8-04
DRAWN	DSA
SHEET #	

S-3

NOOP-TRAINING PLAN